



Open Metering System  
**Conformance Test**

**Volume 3**  
**Data Link Layer**

Issue 4.0.0 / 2016-05-09

Release

## Document History

Version	Date	Comment	Editor
1.0.0	2011-10-11	Final version	J. Feuchtmeier
1.0.1	2012-10-04	Correction of test items [T31-TIM1] and [T31-ACN1] according to OMS AG3 results	J. Feuchtmeier
2.0.0	2013-03-19	Adaption to OMS-S V3.00	J. Feuchtmeier
2.0.1	2013-10-30	Correction of [T31-ACN1]	J. Feuchtmeier
3.0.2	2014-08-14	Test item [T31-TIM1] not mandatory for OMS-CT V2, adopt Table 4 Editorial: change names of test items [T31-TIM2a] and [T31-TIM3a] in Table 4 according headlines Add [T31-TIM4a] as test description	J. Feuchtmeier
3.0.0	2014-10-06	Adopting version number of the OMS-CT to be in line with the corresponding OMS-S version	J. Feuchtmeier
		Asynchronous telegrams shall be detected by the tool [T31-TIM3]	
	2015-02-09	Test description for DLL Address field	J. Feuchtmeier
4.0.0	2015-03-04	Start Version for OMS-CT V4	J. Feuchtmeier
4.0.0.1	2015-04-10	Move section "differences to OMS-S" to OMS-CT General Part	J. Feuchtmeier
4.0.0.2	2015-05-06	Integration of ELL section Using Gateway instead of MUC Using Configuration Field instead of Word	L. Möllendorf J. Feuchtmeier
4.0.0.3	2015-06-17	Integration of Security Profile	A. Seeberg
4.0.0.4	2015-07-03	Generic AFL Test (only for unidirectional meters) Security-Profiles are tested in OMS-CT Vol4, Chapter Security. Moved check for ELL-presence to OMS-CT Vol.4 )	A. Seeberg
4.0.0.5	2015-07-07	Moved AFL and TPL to Vol 4	A. Seeberg
4.0.0.6	2015-10-01	Editorial Work	J. Feuchtmeier
4.0.0	2015-10-16	Version for Enquiry	J. Feuchtmeier
4.0.0	2015-12-16	Version for Vote	J. Feuchtmeier
4.0.0	2016-05-09	Version for Release	J. Feuchtmeier

## Table of contents

<b>1</b>	<b>Scope.....</b>	<b>5</b>
<b>2</b>	<b>References .....</b>	<b>6</b>
<b>3</b>	<b>Definitions, symbols and abbreviations.....</b>	<b>7</b>
<b>Part 1: wireless M-Bus (wMBus) .....</b>		<b>8</b>
<b>4</b>	<b>Test item.....</b>	<b>9</b>
4.1	[T31-MAC1] MAC Test .....	9
4.2	[T31-ADR1] Address structure .....	9
4.3	[T31-C1] Supported C-fields .....	10
4.4	[T31-DC1] Duty Cycle.....	10
4.5	Transmission intervals of meters .....	10
4.5.1	[T31-TIM1] Data telegram .....	10
4.5.2	[T31-TIM2a] Installation telegram .....	11
4.5.3	[T31-TIM3a] Synchronous transmission .....	11
4.5.4	[T31-TIM4a] Transmission of static messages .....	15
4.6	Access number .....	16
4.6.1	[T31-ACN1] Access number meter generic.....	16
4.7	[T31-ELL1] Extended Link Layer .....	16
4.7.1	[T31-ELL2] Consistency of ELL Usage.....	16
4.7.2	[T31-ELL3] Structure of ELL .....	17
4.7.3	[T31-ELL4] Communication Control Field (CC) .....	18
<b>Appendix A: Applicable Test cases of OMS-CT (Normative) .....</b>		<b>19</b>

## List of tables

Table 1: Valid range for parts of meter address .....	9
Table 2: Update interval of consumption data for different media.....	15
Table 3 –Bit values of Communication Control Field (CC) .....	18
Table 4: Test Cases related to DUT type .....	19

# 1 Scope

The present document is a part of the Conformance Test Specification used for certification of equipment according to the Open Metering System (OMS) specification.

This issue is applicable only together with [OMSCT-GEN].

- 5 This document specifies the tests to show conformance for the Data Link layer.

The parameters to be tested, and the test limits are based on OMS Specification Volume 2, Primary Communication [OMSS-Vol2], section 2, *Physical Layer*, section 3, data link layer, section 4, application layer, and the referenced Wireless M-Bus specification [EN 13757-4].

Note:

- 10 This version of test specification does not cover all items of the current OMS Specification.

It is not the scope of this document to show conformance to the essential requirements of the R&TTE directive (1999/5/EC), or other national or international standards.

## 2 References

- 15 The used references are listed in [OMSCT-GEN].

### **3 Definitions, symbols and abbreviations**

The used term definitions, symbols and abbreviations are defined in [OMSCT-GEN] (OMS Open Metering System – Conformance Test Volume 1 – General Part).

# **Part 1:**

## **wireless M-Bus (wMBus)**



## 4 Test item

All tests shall be done in a low collision scenario. Transmissions of other devices than DUT shall be less than 2% channel occupation.

### 4.1 [T31-MAC1] MAC Test

The following items shall be tested:

- L-Field
- CRC
- Channel coding
- Bit Order
- Frame Format and Synchronization sequence
- Preamble length
  - Mode T1, T2, S1, C1 and C2: short and long preamble
  - Mode S2: long preamble

All items shall be conforming to [EN 13757-4].

### 4.2 [T31-ADR1] Address structure

**Applies to: unidirectional meter, bidirectional meter, unidirectional repeater, GW**

It shall be verified that the address of the Link Layer is compliant with the requirements given in Table 1: Valid range for parts of meter address Table 1:

Byte number	Content	remark
Byte 1..2	Manufacturer	Binary (binary coded 3-Letter Manufacture ID as listed by Flag association) <sup>1</sup>
Byte 3..6	Ident number	BCD only (from 00000001 to 99999999)
Byte 7	Version	Binary (from 00h to FEh)
Byte 8	Device type	Binary (all values from [EN 13757-3] Table 3 and [OMSS-Vol2] Table 10)

**Table 1: Valid range for parts of meter address<sup>2</sup>**

<sup>1</sup> Manufacturer must be listed in [FLAG]. The three letters of Manufacturer ID can be derived by calculation given in [EN13757-3] clause 5.5.

<sup>2</sup> The content is in different sequence as in [T41-AD1] of [OMSCT-APL]

### 4.3 [T31-C1] Supported C-fields

**Applies to: unidirectional meter, bidirectional meter**

55 The devices shall support C-field 44h.

If installation telegrams are supported (see [OMSCT-ManDec]) C-Field 46h shall be used to transmit installation telegrams.

All C-Fields shall be used only in context with message types according [OMSS-Vol2] Table 10 and [OMSS-Vol2] Table 11.

### 4.4 [T31-DC1] Duty Cycle

**Applies to: unidirectional meter**

The duty cycle, as defined in [EN 300 220-1] chapter 7.10.1, shall comply with the following limits:

S1 mode (meter): Maximum 0,02 %

65 S2 mode (other): Maximum 1 %

T1 mode (meter): Maximum 0,1 %

T2 mode (other): Maximum 1 %

C1 mode (meter): Maximum 0,1 %

C2 mode (other): Maximum 10 %

70 The Duty Cycle of the meter shall be observed over a period of exact 1 h.

The Time Period shall be started with a telegram transmission.

The telegram length determination shall include preamble, coded message part and checksum's of all telegrams within the observation period.

### 4.5 Transmission intervals of meters

#### 4.5.1 [T31-TIM1] Data telegram

**Obsolete, used in earlier OMS-CT generations.**

It shall be verified by using a sniffer tool that:

- the device under test sends meter data (C-field = 44h) at least every {7,5, 30 or 240} minutes (depending on media) (refer to [OMSS-Vol2], Tab 1)
- 80 ▪ The maximum tolerance of 10 received individual transmissions are <= 40% of the stated transmission interval (refer to [OMSCT-ManDec]):

$$\frac{MAX(T\_1...T\_9) - MIN(T1...T9)}{T\_set} \leq 40\%$$

- The typical tolerance of 10 received individual transmissions is >= 1% of the stated transmission interval (refer to [OMSCT-ManDec]):

$$\frac{\sum_{i=1}^9 T_i}{9} * \frac{1}{T\_set} \geq 1\%$$

85

- The standard deviation of 10 received individual transmissions is  $\geq 12\%$  of the stated transmission interval (refer to [OMSCT-ManDec]):

$$StdDev(T_1 \dots T_n) * \frac{1}{0,2 * T_{set}} \geq 12\%$$

90 Abbreviation's for all calculations of [T31-TIM1]:

T<sub>set</sub>: stated transmission interval in [OMSCT-ManDec]

T<sub>n</sub>: measured transmission interval (n= 1...9)  
(over 10 transmissions)

StdDev: standard deviation

95 MIN: minimal value

MAX: maximal value

## 4.5.2 [T31-TIM2a] Installation telegram

**Applies to: unidirectional meter, bidirectional meter**

100 Reference:

- OMS, Vol2, Issue 4.0.2 / 2014-01-27, chapter 4.2.2.3
- DIN EN 13757-3 (2013) / Annex O.2

- The manufacturer has to define whether the DUT transmit installation telegrams or not [OMSCT-ManDec] and how to start the transmission of installation telegrams
- 105 ▪ Initialize DUT and set it to begin with transmissions

It shall be verified by using a sniffer tool that:

- the device under test transmits at least 6 installation telegrams (C-field = 46h) with an interval of 30 to 60 seconds
- transmit of installation telegrams stopping not later than 60 minutes after the manual start event
- 110 ▪ the configuration field shall be set to static message ([OMSS-Vol2] ch.7.2.4.6 Tab.24.) if the installation telegram contains fixed data for meter management. ([EN 13757-3:2013] Annex O.2)

Otherwise → ERROR

115 The verifying has to be performed if no installations telegrams declared by manufacturer although the device transmits those. The information has to be notified in the test report.

## 4.5.3 [T31-TIM3a] Synchronous transmission

**Applies to: unidirectional meter, bidirectional meter**

120 Reference:

- [OMSS-Vol2], chapter 4.2.2.1
- [EN 13757-4], chapter 11.6.2

### Test of Manufacturer Declaration:

- 125
- $t_{NOM}$  must be defined by manufacturer (in Manufacturer Declaration)
  - $t_{NOM}$  must be  $N \times 2$  seconds with  $N > 1$  and

Mode	max $t_{NOM}$
S-Mode	90 min
T-Mode	15 min
C-Mode	15 min

- 130
- Min and max test-temperatures are the operation temperatures, and must be declared in the R&TTE test report.
  - For device types 04h (heat), 05h (steam), and 0Ch (heat, volume measured at flow temperature inlet) the manufacturer must state whether the device is used for “district heating” or “sub metering”. Depending on this information the maximum average update interval is set.

135

### The following steps shall be run through for the test:


1. Initialize DUT and set it to begin with transmissions
  2. Place DUT in temperature chamber. Set start-temperature to 20°C.
  - 140 3. Wait until temperature in chamber has stabilized.
  4. Set Ident. No., manufacturer, version, and device type of DUT in test-tool. Using this information the test-tool shall only monitor the DUT. Other devices shall not be monitored.
  5. Start the test-tool and monitor the transmissions for at least 24 hours.
- 145
- Accept only devices with the defined identification and message types SND\_NR (44h), ACC-DMD<sup>3</sup> (48h) or ACC-NR (47h)
  - Transmissions must be monitored with a time-resolution of 1ms.
  - Deviation of the time of the test-system compared to world-time must not exceed 0.1s over 24h.

---

<sup>3</sup> ACC-DMD can only be used for bidirectional devices

150

6. During test, cool and heat the DUT using the following ramp:




Min and max temperatures are taken from the R&TTE report.

Keep relative humidity below 10%.

7. After monitoring, analyse received transmissions:

155

- a. Check the allowed tolerance by the following scheme over the observation period (informative – not relevant for approval):



160

The time between synchronous transmissions with set S-bit in configuration Field shall be:

$$t_{TX}(n+1) = t_{TX}(n) + t_{ACC}(n+1)$$

$$t_{ACC}(n+1) = (1 + (|ACC(n) - 128| - 64) / 2048) \times t_{NOM}$$

The tolerance for  $t_{TX}$  must be

165

- $t_{PosTol} = +110$  ppm  
 $t_{NegTol} = -30$  ppm  
 for meters operating in the temperature range -15 ... +65°C

- $t_{PosTol} = +230$  ppm
- $t_{NegTol} = -30$  ppm
- for all other meters

The tolerance is accumulated over the observation period.

The  $t_{PosTol}$ ,  $t_{NegTol}$  shall be in tolerance for two following transmissions.

The operating temperature is taken from the R&TTE report.

The additional jitter for  $t_{TX}$  must be:

- non accumulative
- $t_{Jitter} = +/-1$  ms for  $t_{NOM} < 300$  sec
- $t_{Jitter} = +/-3$  ms otherwise

- b. Check the tolerances between adjacent transmissions using the tolerances described above.

If time-interval is out of tolerance → ERROR

- c. Check whether for every synchronous transmission the access counter was incremented by one.  
Otherwise → ERROR

If a synchronous transmission is omitted by the device under test or missed by the sniffer tool, then the access counter must be incremented by one as if the transmission had occurred.

- d. If the OMS-CT Tool detects asynchronous transmissions (S-bit not set in configuration field) then:

Confirm that asynchronous transmissions do not alter the access counter.

Otherwise → ERROR

- e. Check whether the rate of omitted synchronous transmissions over a (sliding) 24hour period does not exceed 6.25%.  
Otherwise → ERROR

During test no other transmitters shall interfere with the test condition.

- f. Check whether a synchronous transmission with message type SND-NR is transmitted in a time-interval less or equal to  $T_{update}$  (depending on metering media, see Table 2).

Otherwise → ERROR

- g. If synchronous transmissions with message types ACC-NR (or ACC-DMD) are transmitted in between of synchronous transmissions with message type SND-NR then:

210

- Count the number of transmissions with types ACC-NR (or ACC-DMD) that are transmitted in between of synchronous transmissions with message type SND-NR.
- Check whether the ratio n/1 for ACC-NR (or ACC-DMD) to SND-NR telegrams does not change and is within 0/1 to 15/1.  
Otherwise → ERROR

215

Metering media	Media number	Average update interval maximum [min], $T_{\text{update}}$
Electricity	02h	7.5
Gas	03h	30.0
Heat (district heating)	04h, 05h, 0Ch	30.0
Water / Warm water	06h, 07h, 15h, 16h, 17h	240.0
Heat cost allocators	08h	240.0
Heat / Cold (sub metering)	04h, 05h, 0Ah, 0Bh, 0Ch, 0Dh	240.0
Repeater	32h	240.0

**Table 2: Update interval of consumption data for different media**

220

#### 4.5.4 [T31-TIM4a] Transmission of static messages

**Obsolete, prepared for future OMS-CT generations.**

Reference:

- OMS, Vol2, Issue 4.0.2 / 2014-01-27, chapter 4.2.2.4

225

- The manufacturer has to define whether the DUT transmit static messages or not [OMSCT-ManDec]

If the manufacturer stated that static telegrams are used, then it shall be verified by using a sniffer tool that:

230

- the device under test transmit at least two static telegrams within a test period of 24 hours
- the static messages are signalled by the configuration field according [OMSS-Vol2] ch.7.2.4.6 Tab.24.

Otherwise → ERROR

235

If the manufacturer does not state that static telegrams are used, but static telegrams are received during the test, then the verifying and reporting has to be performed as if static telegrams had been stated by the manufacturer.

## 4.6 Access number

### 4.6.1 [T31-ACN1] Access number meter generic

**Applies to: unidirectional meter, bidirectional meter**

It shall be verified using a sniffer tool that the access number of at least 6 transmissions in a row of the device under test is incremented by 1 from one new synchronous transmission to the next.

It has to be verified that the Access Number is increased by at least one at least once in the visualisation interval given in [OMSS-Vol2] Table 7.

It shall be verified using a sniffer tool that all SND-IR messages sent after a manual installation start event are using the same access number as used in the latest new telegram.

## 4.7 [T31-ELL1] Extended Link Layer

In case the ELL is present at least in one transmission within the observation periode, [T31-ELL2] to [T31-ELL4] shall be applied.

In case the ELL is never present in the transmissions within the observation periode [T31-ELL2] to [T31-ELL4] shall be skiped.

### 4.7.1 [T31-ELL2] Consistency of ELL Usage


The CT Tool shall check for each transmission within the observation period if it contains an ELL.

The CT Tool shall test if the ELL is present in any (all) transmissions in the observation period. Otherwise the test shall fail.



## 4.7.2 [T31-ELL3] Structure of ELL

To test the validity of the ELL structure as defined in [OMSS-Vol2] chapter 5.3.2 the tests in the flow chart shall be applied:



### 4.7.3 [T31-ELL4] Communication Control Field (CC)

The Communication Control Field (CC) shall be conforming to [OMSS-Vol2] chapter 5.3.3 according to Table 3:

Bit Nr	Bit(s)	Description	Test specification
7	B	Bidirectional Communication	This bit shall always be 0b. <sup>4</sup>
6	0	Delay	This bit shall always be 0b.
5	S	Synchronous	This bit shall be 0b or 1b
4	H	Hop Counter	This bit shall always be 0b <sup>5</sup>
3	0	Priority	This bit shall always be 0b
2	A	Accessibility	This bit shall always be 0b <sup>6</sup>
1	R	Repeated Access	This bit shall always be 0b <sup>7</sup>
0	0	Reserved	This bit shall always be 0b

270 **Table 3 –Bit values of Communication Control Field (CC)**

If at least one of the tests fails this test shall fail.

<sup>4</sup> Currently only unidirectional meters are tested.

<sup>5</sup> The bit H is used as a Hop Counter to indicate a repeated transmission. The meter, actuator or gateway shall transmit bit H always with zero.

<sup>6</sup> Currently only unidirectional meters are tested.

<sup>7</sup> The bit R is reserved for use in repeated messages. The meter or actuator shall transmit bit R always with zero. A meter/actuator may ignore a received bit R.

## Appendix A: Applicable Test cases of OMS-CT (Normative)

### 1. Test cases of Wireless M-Bus devices

Test case	Description	UDM <sup>1)</sup>	BDM <sup>2)</sup>	UDR <sup>3)</sup>	GW <sup>4)</sup>
[T31-MAC1]	MAC Test	X	X	X	X
[T31-ADR1]	Address structure	X	X	X	X
[T31-C1]	Supported C fields	X	X		
[T31-DC1]	Duty Cycle	X			
[T31-TIM1]	Transmission intervals of meters: Data Telegram				
[T31-TIM2a]	Transmission intervals of meters: Installation Telegram	X	X		
[T31-TIM3a]	Transmission intervals of meters: Synchronous Transmission	X	X		
[T31-TIM4a]	Transmission of static messages				
[T31-ACN1]	Access number generic	X	X		X
[T31-ELL1]	Extended Link Layer	X	X		X
[T31-ELL2]	Extended Link Layer - Consistency	X	X		X
[T31-ELL3]	Extended Link Layer – Structure	X	X		X
[T31-ELL4]	Extended Link Layer – Control Field	X	X		X
Note: X This Test case is mandatory 1) UDM = Unidirectional Meter 2) BDM = Bidirectional Meter 3) UDR = Unidirectional Repeater 4) GW = Gateway					

**Table 4: Test Cases related to DUT type**

